

Bill of Quantaties (BoQ's)

**REPAIR & RENOVATION OF OTP SITES, PARTITION WORKS AT IN
BHCIP FOCUSED HEALTH FACILITIES**

Bill of Quantaties (BoQ's)

items	DESCRIPTION	QUANTITY	UNIT	RATE	AMOUNT
				(Pak Rs)	(Pak Rs)
1	Providing and fixing 1.25" (32mm) thick First class deodar wood partition fully panelled with the same wood as required including beadings and deco paint etc complete in all respect as per the directions of engineering in charge.				
1.1	REPAIR & RENOVATION OF OTP SITES, PARTITION WORKS AT MUFTI MEHMOOD MEMORIAL HOSPITAL KUCHLAK QUETTA	104.00	Sft		
		88.00	Sft		
1.2	REPAIR & RENOVATION OF OTP SITES, PARTITION WORKS AT BHU MUHAMMAD KHAIL PANJPAI QUETTA	96.00	Sft		
		64.00	Sft		
1.3	REPAIR & RENOVATION OF OTP SITES, PARTITION WORKS AT RHC NOKUNDI DISTRICT CHAGHI	120.00	Sft		
		88.00	Sft		
1.4	REPAIR & RENOVATION OF OTP SITES, PARTITION WORKS AT DHQ PRINCE FAHAD HOSPITAL DALBANDIN DISTRICT CHAGHI	104.00	Sft		
		136.00	Sft		
1.5	REPAIR & RENOVATION OF OTP SITES, PARTITION WORKS AT BHU SAGAI DISTRICT KILLA ABDULLAH	104.00	Sft		
		64.00	Sft		
1.6	REPAIR & RENOVATION OF OTP SITES, PARTITION WORKS AT BHU TORA SHAH DISTRICT PISHIN	101.60	Sft		
		72.00	Sft		
1.7	REPAIR & RENOVATION OF OTP SITES, PARTITION WORKS AT OF DHQ PISHIN	128.00	Sft		
		104.00	Sft		
1.8	REPAIR & RENOVATION OF OTP SITES, PARTITION WORKS AT RHC SHAHDEZAI AT DISTRICT PISHIN	96.00	Sft		
		64.00	Sft		
		1533.60	Sft		
				TOTAL	